

R806 Main Street Island Removals Phase 2

A route for pedestrians will be maintained throughout island works

Filter lane closed with traffic for Clonsilla Road going to right of island

TM plan assumes that roadworks end signage is already at exits from concurrent works

Use this approach signage if it is not already in place for concurrent works

